

## THE DISTRICT COUNCIL OF PAMPLEMOUSSES

### NOTICE BID OPENING

#### PROCUREMENT FOR THE SUPPLY, LAYING AND COMPACTING OF ASPHALTIC CONCRETE (RESURFACING OF ROADS)


(Reference: DCP/ONB/02/2020-21)

It is hereby notified that the bids received for the above mentioned procurement exercise were opened at the District Council Office on **Friday 31 July 2020 at 14.30 hrs** as detailed hereunder:

SN	DESCRIPTION OF WORKS	UNIT	RATE (RS) - (VAT INCLUSIVE)			
			GAMMA CONSTRUCTION LTD	J. DOOKHUN & SONS LTD	SAFETY CONSTRUCTION CO LTD	TRANSINVEST CONSTRUCTION LTD
	<b>DCP/ONB/02/2020-21 - Supply, Laying and Compacting of Asphaltic Concrete (Resurfacing of Roads)</b>		Royal Road, Chapman Hill, Beau Bassin	Royal Road, Petite Riviere	Royal Road, Camp de Masque Pave	39-41, Richelieu Branch Road, Coromandel
1	Cleaning of site & leveling. The whole surface should be cleaned and cleared of all loose soil, debris, etc.	M <sup>2</sup>	29.90	5.	28.50	37.95
2	Application of a Prime coat/Tack coat at the rate of 0.6 kg/m <sup>2</sup> with cationic emulsion.	M <sup>2</sup>	35.54	35	40.80	40.25
3	Supply and placing of bituminous asphaltic concrete base course of grading 0/14 with 4.6% bitumen content and compaction of the same and associated works with regards to the reshaping of the road as and where required to fill depressions and pot holes. <b>(Provisional bituminous asphaltic concrete)</b>	Ton	4,455.10	2500	5,576	4,674.75
4	Supply and placing of 40 mm thick bituminous asphaltic concrete wearing course of grading 0/10 with 5.6% bitumen content and compacting of the same and associated works.	M <sup>2</sup>	461.27	750	557	520.95
5	The price quoted for this item shall include:- Preliminary cleaning and marking out the pavement; Supply of road marking material (Thermoplastic Paint Material). Painting of existing road surface as directed by the					

	Project Manager. Supply of traffic cones, temporary traffic signs for the proper regulation of traffic as directed by the Project Manager. Any miscellaneous cost, which may arise <b>(Provisional remarking of road surface)</b>					
5A.	<b>White hot melt thermoplastic 1.5 mm thick.</b>	M <sup>2</sup>	633.42	500	938	778.55
5B.	<b>Yellow hot melt thermoplastic 1.5 mm thick.</b>	M <sup>2</sup>	679.88	500	1,028	795.80

Date: **31 July 2020**

  
 .....  
**J.F Dorestan**  
**Chief Executive**